KADUR DIVISION.

Dated 6th June 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 1st July 1929, for constructing a New Dispensary at Javali, Mudgere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed within four months from the date of acceptance of tender.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 600 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for constructing a New Dispensary at Javali, Mudgere Taluk " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimated amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after the acceptance of tenders.

11. Rates should be quoted for each item of work and lumpsum rates are subject to modification as per data worked out during execution.

Estimate for constructing a Dispensary with quarters for staff at Javali, Mudgere Taluk.

No.	Items of work	Per	Quantity
	Local Fund Dispensary.		
1	Earthwork excavation and filling in basement	C.yd.	74
2	Stone jelly concrete for foundation	C.ft.	1,015
3	Burnt size stone in mortar	,,	1,333
4	Burnt brick in mud	,,	2,555
5	Burnt brick in mortar	,,	589
6	Cuddapah slab flooring on parapets, etc.	S.ft.	56
7	Teakwood door battened with strong hinges, tower, bolts, hinged stoppers and locking arrangements.	,,	137
8	Teakwood window half panelled and half glazed single shutters with iron bars, hinges, hooks, etc.	,,	96
9	Teakwood shelves with 1" planks and shutters, etc. ...	,,	16
10	Teakwood cup boards with pegs	R.ft.	36
11	Teakwood eave boards plain	,,	144
12	Teakwood hand gate with iron works	S.ft.	16
13	Burnt stone slabs roughly dressed	,,	107
14	Teakwood pendents	Each	4
15	Honne or Mathi wood work wrought and put up ...	C.ft.	64·67
16	Roofing with First Class Mangalore tiles on teak reepers, etc.	Square	12·18
17	Ridge tiles set in mortar and cement pointing	R.ft.	71
18	Chunam mortar plastering	Square	46·02
19	White washing two coats	,,	46·02
20	Tarring wood work	,,	2·00
21	Wood oiling two coats	,,	6·00

No.	Items of work	Per	Quantity
22	Chocolate painting (exposed portion only)	Sqr.	3·40
23	Providing sinks and chains	Each	2
24	Flooring with Mangalore tiles on 3" concrete bed and cement pointing.	Sqr.	5·33
25	Providing stone jelly concrete drain	R.ft.	28
26	Flooring with Cuddapah slabs on 3" concrete bed cement pointing.	Sqr.	1·66
27	Burnt stone slab pillars including cutting grooves and champer edges, etc.	Each	4
28	Clearing site forming road hedge with gate and compensation for land, etc.	Lump	sum
29	Constructing a latrine as per design	Lump	sum
	Assistant Surgeon's Quarters.		
1	Earthwork excavation and filling in basement	C.yd.	54
2	Stone jelly concrete for foundation	C.ft.	741
3	Burnt size stone in mortar foundation and basement ...	,,	965
4	Burnt brick in mortar	,,	2,619
5	Burnt stone slabs dressed 4" to 6" thick	Sq.ft.	89
6	Cuddapah slabs	,,	18
7	Teakwood door battened with 3 tower bolts hinges hinged stoppers, etc., complete.	,,	91
8	Teakwood window single side shutters battened with 5/8" iron bars, with four halves rings, etc , complete.	,,	84
9	Teakwood shelves one in kitchen and one in room with cross planks 1" thick and shutters with locking arrangement.	,,	16
10	Teakwood cup board in kitchen	,,	6·5
11	Teakwood work wrought and put up	C.ft.	50·77
12	Roofing with First Class Mangalore tiles on reepers ...	Sqr.	8·62
13	Ridge tile set in mortar	R.ft.	71
14	Chunam plastering	Sqr.	37·44
15	White washing two coats	,,	37·44
16	Tarring wood work imbeded in walls, etc.	,,	2·00
17	Wood oiling two coats	,,	3·00
18	Chocolate painting	,,	2·00
19	Providing bath with 1' stone wall in surki mortar and burnt stone slab flooring on 3" stone jelly concrete bed and cement pointing.	Lump	sum
20	Flooring with Mangalore tiles, etc.	Sqr.	4·00
21	Gravel flooring with cowdung wash	,,	0·56
22	Mortar and pestle stones	Set.	2
23	Constructing drain in stone jelly cement concrete and providing bamboo hedge.	Lump	sum
24	Constructing a latrine as per design	Lump	sum
	Kitchen.		
1	Earthwork excavation and filling in basement	C.yd.	9
2	Filling foundation with stone jelly concrete	C.ft.	96
3	Burnt stone in mortar (sized)	,,	195
4	Burnt brick in mortar	,,	408
5	Surki plastering	Sqr.	5·52
6	Flooring with Cuddapah slabs over 3" concrete bed and cement pointing.	,,	0·70
7	Teakwood work wrought and put up	C.ft.	13·11
8	Roofing with First Class Mangalore tiles on teak reepers including chunam borders at ends, etc.	Sqr.	2·56
9	Pointing with cement (basement)	,,	0·48
10	Ridge tile (ordinary) set in mortar	R.ft.	16
11	Ventilating tiles (glazed)	Each	4
12	Burnt stone slabs 6" dressed roughly	Sq.ft.	16
13	Teakwood battened door with bolts, hinges and iron clamps, etc., complete.	,,	18
14	Teakwood battened window with iron bars and fillings, etc., complete.	,,	5
15	Chocolate painting to doors and windows	Sqr.	0·46
16	Clearing site and levelling ground	Lump	sum

No.	Items of work	Per	Quantity
	Latrine.		
1	Earthwork excavation and filling in basement	C.yd.	6
2	Stone jelly concrete for foundation	C.ft.	86
3	Burnt size stone in mortar	„	86
4	Burnt brick in mortar	„	378
5	Coping over wall complete with plastering	R.ft.	42
6	Small stone jelly surki concrete flooring	C.ft.	11
7	Rendering with cement	Sqr.	0·35
8	Surki mortar plastering	„	5·00
9	Stone jelly cement concrete sinks	C.ft.	3
10	Constructing drain in jelly 3" with cement plastering, etc., complete.	R.ft.	20
11	Clearing site and levelling	Lump	sum

Abstract Notification dated 5th June 1929.

"The attention of the Depositors and their heirs is drawn to the notice published on pages 573 & 574, dated 23rd May 1929, Part IV of the *Mysore Gazette*. The amounts if not claimed before the 30th of this month will lapse to Government".

B. KRISHNA RAO,
Executive Engineer.

SANITARY AND TOWN PLANNING DIVISION, BANGALORE.

Abstract Notification dated 27th May 1929.

The attention of the public is invited to the detailed Notification calling for sealed tenders for laying pipe line in connection with the water-supply to Hunsur Town, published on pages 526-527 of Part VI of the *Mysore Gazette*, dated 30th May 1929.

The last date for the receipt of tenders is 2 P.M., of 1st July 1929.

H. F. MARKER,
Executive Engineer

KOLAR DIVISION.

Notice dated 21st May 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 509-510, dated 30th May 1929, calling tenders for opening a Feeder Channel from Ablodu tank to Sidlaghatta Ammanakere, Sidlaghatta Taluk. The last date of tender is 14th June 1929.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE RAILWAYS, MYSORE.

Abstract Notification dated 31st May 1929.

Attention of the intending contractors is invited to the notice calling for sealed tenders for the construction of Foundary Shop at Central Workshops, Mysore, published in pages 515 and 516 of Part VI of the *Mysore Gazette*, dated 30th May 1929. Tenders will be received on any working day up to 2 P.M. of 1st July 1929.

M. RAMAIYA,
Executive Engineer.